



INFRARED HEATING REQUIREMENTS

1. (8) LTU100-30 VENTED SPACE-RAY INFRARED HEATERS. INSTALL AT 18 FEET ABOVE THE FINISHED FLOOR.
2. (3) SPACE-RAY SETBACK 5000 THERMOSTATS MOUNTED 56" ABOVE THE FINISHED FLOOR.
3. HEATERS SHALL BE "PULL THROUGH" SYSTEMS (VACUUM) WITH CAST IRON BURNER AND CALORIZED EMITTER TUBES.
4. HEATER, THERMOSTAT LOCATIONS SUBJECT TO FIELD VERIFICATION & COORDINATED WITH OTHER EQUIPMENT IN THE BUILDING.
5. CONSULT HEATER SPECIFICATION SHEET AND "I & O" INSTRUCTIONS FOR FURTHER INFORMATION PLEASE VISIT WWW.SPACERAY.COM
6. HEATERS MAY BE SIDEWALL OR ROOF VENTED.
7. INSTALL PROPER SECOND STAGE REGULATORS AND VENTS IF ABOVE 1/2PSIG GAS SUPPLY.



Title: **SAMPLE WAREHOUSE**
LINCOLN, NEBRASKA

Drawn By: **RJ Herrington**

Date: **20 MAR 07**